G. R. S. 59 GPB—15,000—22-7-14

GENERAL AND REVENUE SECRETARIAT.

1900
~~191~~
(L B)

File No. 91 of 1900

Serial Nos. 1—2

~~Papers Filed.~~

Month March 1901

SUBJECT.

Construction of a well at Anidenahalli village, Kadur Taluk

Indexed — Rabbarao

PREVIOUS REFERENCES.	LATER REFERENCES.
3-782 1899	Condemnation L.S. Rao

97

L645
1901
~~97~~

10393 ~~189~~
16 Mar: 01

From The President of the
Local Fund Board
Kadur Circle

To The Secretary to the
Government of Mysore
General & Rev: Department

SECTION L.B
FILE No. 91 of 1900
SERIAL No. 1

To the Dewan: etc
No 12736/8 29/3/

Dated 15th March 1901

Despatched

Received

General No. 555
No.

Enclosure No. 3

Submitting a revised Estimate
for Rs 793/- for constructing a
Square well at Andenahalli
village in the Kadur Taluk for
favor of Government Sanction

16.3.01

A. S. Char
19/3/01

~~Draft~~ put up
20/3

1900-1901

Kadur District Local Fund Board
President's Office
Dated Chikmagalore 15th March 19

From

H. H. Sparkes Esqre
President of the
Local Fund Board
Kadur Circle

To

The Secretary to the
Government of Mysore
General & Revenue Departments.

Sir.

I have the honor to submit herewith for favor of Government sanction a revised estimate for Rs 793/- for constructing a square well at Andenahalli village in the Kadur Taluk.

2 The original Estimate sanctioned by the President in the month of March 1900 was for Rs 484/- and the depth of the well as per original Estimate was 48 ft, which is also enclosed for favor of perusal

3 The Assistant Commissioner in charge of the Northern division after inspecting the work reports that though the well has been sunk to a depth of 48 ft and water has just been tapped, the well will have to be deepened 10 ft more to ensure an unfailing supply of water for the use of the villagers. Hence the revised Estimate.

The Excess of Rs 309/- over the original Estimate may e met out of Rs 5000/- Sanctioned in G.O. No: 1757-8 / LF 15-99 ated 3-8-1900. A copy of the abstract of the revised timate is enclosed.

A: 17

I have the honor to be,
Sir
Your most obedient Servant

The revised estimate for conovincing a Square well at Andenahalli village in the Kadur Taluk —

Abstract A

Items	Per	Rate	Quantity	Amount
Earth work Excavation	Cyd	a 4	80	20
Blasting Rock from 30 ft up to 45 ft	Cyd	4 –	45	180 –
Do up to 60 ft	– Do –	6 –	31¼	187 –
rurnt Stone Slabs dressed	sqft	a 6	350	131 –
Pulleys with iron works —	no:	5 –	2	10 –
Burnt stone lining	Cyd	3 –	80	240 –
Packing Earth	– Do –	2	40	5 –
Levelling the ground and Bailing water &c —	LS.			20 –
Total value of the Estimate			Rs –	793 –
Deduct amount already Sanctioned			Rs	484 –
Net amount to be Sanctioned by Government				309 –

Rupees three hundred and nine only

Chickmagalur
11th March 1901

H. H. Sparks
[illegible]

4 99 ~~101~~

L. B
91 of 1900
SER 2

Read

Letter no. 555 dated the 10th March 1901 from the President of the D. T. Board Kadur D. T. circle stating that an estimate for Rs 482/- ~~was sanct~~ for sinking a well at Andenahall in the Kadur Taluk was sanct by the President and the well sunk to a depth of 40 the depth provided for in the estimate, and that althoug water has been tapped at tha depth a further deepening by 10 ft is considered necessary to ensure an unfailing ~~sply~~ supply of water, and submit ting a revised estimate for Rs 793/ for the same rders No: $\frac{12736-37}{L.F. 15-99}$ d 29/3/07.

In: 2 B.F.
& one of Compt—

R.L. 1728

The revised estimate

eceived with the above is

anctioned

The extra cost of

Rs 309/- after deducting

the amount of original

estimate will, as proposed,

he met from the sum of

Rs 5000/- sanctioned from

the L.F. Fund in Govt Procs:
vide L.B. 7 83-4 8-10 [illegible] 7;

No. $\frac{1757-8}{L.F. 15-99}$ of the 3d Aug 1900

Ms
26/3/07

27/3/07

Under Secty.

Despd 31/3/07

To

The Presd: D.F.Bd Kadur circle
returning the sanctd estimate
[illegible] with copy of abstract estimate